

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>36</u> N. S., R. <u>27</u> E. W.	<u>C-7, D-7, D-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on September 12 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-7 N.W. Section corner - Section 20; Wood post, Hem. 10 - N37°W - 25 lks., Hem. 12 - S46°E - 29 lks.
- D-7 North ¼ corner - Section 20; Wood post, Hem. 14 - N35°W - 35 lks.; Cedar 10 - S76°E - 19 lks.
- D-9 South ¼ corner - Section 20; Wood post, W. Pine 14 - N41°W - 27 lks.; W. Pine 20 - S67°E - 21 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-7 Set at old fence corner. Fence N-e & W. A line of hemlock knots indicate a hemlock once stood in approximately the right position for the S.E. O.B.T.
- D-7 Set in centerline of N-S black top road and in line with the centerline of a road east.
- D-9 Set in the center of N-S black top road and in line with very old fence east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-7 1" pipe, 4" aluminum cap; 3" Sugar Maple - N17°E - 26.0'; 5" Red Oak - S44°E - 35.6'; 12" W. Spruce - S35°W - 38.8'; 5" Sugar Maple - N37°W - 21.8'.
- D-7 ½" pipe & plastic RLS cap; 5" Cedar - N38°E - 82.8'; Power Pole - N34°E - 60.4'; 4" Cedar - N74°W - 40.2'; 6" Cedar - S88°W - 58.6'.
- D-9 ½" Pipe with plastic RLS Cap; 14" W. Pine - S35°W - 51.0'; 18" W. Pine - S54°W - 66.0'; Power pole - N65°E - 34.8'; Southwest corner of barn - S89°E - 176.0'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR DATE 10-11-79  
 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558