

Menominee Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>36</u> N. S., R. <u>27</u> E. W.	<u>A-10, C-10</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 24 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-10 West $\frac{1}{4}$ corner; Wood post - Hem. 4 - S79°W - 11 lks.; Hem. 6 - N44 $\frac{1}{2}$ °W - 27 lks.
- C-10 E $\frac{1}{4}$ corner - Section 30; Wood post - Fir 10 - N64°W - 22 lks.; Fir 10 - S45°E - 35 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-10 Set at old gate post on north side of driveway and in old N-S fence line - Mr. Louis Berglin who was born and raised on and now owns the property to the East, says the gate post was set at the $\frac{1}{4}$ corner as marked by survey in 1911 and he remembers the N.W. O.B.T. being in place when he was younger. He was born in 1916.
- C-10 Found very old 4" x 4" square cedar post, at fence corner. Not of record but fits surrounding corners and occupation well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-10 1" pipe, 4" aluminum on north edge of driveway; W. Pine - N19°W - 78.55'; Nail & Brass Cap in Face of P. Pole - N36°W - 97.35'; Nail & Brass Cap in Face of P. Pole - S42°W - 117.7'; Centerline N-S Road - West - 101'.
- C-10 1" pipe, 4" aluminum cap; 4" Cedar - N29°E - 9.7'; 8" Cedar - N71°W - 7.8'; 9" Cedar - S6°W - 31.7'; 4" Twin Cedar - S65°E - 19.7'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt DATE 10-11-79
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558