

Menominee Co

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>36</u> N. S., R. <u>27</u> E. W. | <u>H-7, I-7</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>22</u> | T. <u>36</u> N. S., R. <u>27</u> E. W. | <u>2</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 7 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-7 North $\frac{1}{4}$ corner - Section 22; Wood post, W. Pine 30 - N35°W - 66 lks.; W. Pine 30 - S28°E - 29 lks.
- I-7 N.E. Section corner - Section 22; Wood post - Cedar 16 - N59°E - 66 lks.; Cedar 10 - S76°W - 21 lks.
- 2 E 1/16 corner on the north section line - Section 22; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-7 Set M.P.O.L. between the N.E. and N.W. section corners of Section 22.
- I-7 Found old square cedar post and point of another beside it. Stp. remains in place for S.W. O.B.T. and cedar stub, down, in place for N.E. O.B.T. both burned. N.E. one still shows signs of old scarring. Living cedar with old blaze facing stake 6.6' S39°W - replaced with D.N.R. monument.
- 2 Set M.P.O.L. between the N $\frac{1}{4}$ corner and the N.E. section corner of Section 22

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL - 1" pipe, 4" aluminum cap.
- H-7 7" Spruce - N36°E - 30.4'; 8" W. Birch - N69°E - 25.7'; 5" Maple - S52°E - 12.4'; 6" Balsam - S40°W - 9.2'.
 - I-7 10" Cedar - N14°E - 14.2'; 8" Cedar - S62°E - 17.0'; 8" Cedar - S39°W - 6.6'; 9" Cedar - N58°W - 9.65'.
 - 2 4" Spruce - N18°W - 14.9'; 4" Spruce - N54°E - 3.4'; 8" Maple - S57°E - 9.8'; 8" W. Birch - S11°W - 9.7'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR DATE 10-11-79 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558