

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>36</u> N. S., R. <u>27</u> E. W.	<u>D-5, E-5</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 13 1979 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- D-5 N 1/4 corner - Section 17; Wood post, Cedar 14" - N24°W - 17 lks.; Cedar 6" - S38°E - 23 lks.
- E-5 N.E. Section Corner - Section 17; Wood post, Beech 10 - N20°E - 37 lks.; Lynn 12 - S52°W - 49 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-5 Set in line with (12.86) centerline of road south and east and in line with old fence vest.
- E-5 Set monument at old fence corner - no other evidence of true corner position available. Fits location of surrounding corners well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ALL - 1" pipe, 4" aluminum cap.

- D-5 9" Cedar - N24°W - 36.5'; 5" W. Spruce - N24°E - 56.1'; Guy Pole - S35°W - 44.9'; Power Pole - S45°E - 54.3'.
- E-5 5" B. Cherry - S38°E - 18.5'; 4" W. Ash - S21°E - 20.5'; 7" Sugar Maple - N35°E - 71.4'; 5" Sugar Maple - N66°E - 64.8'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 10-11-79
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558