

**SURVEY & REMONUMENTATION**

APR 06 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Four Group Under Act 345 of  
P.A. of 1990 On 6/26 1998  
Mel Davis RLS  
Chairman

For corners in

MENOMINEE  
(County)

Located In: Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>36</u> N <u>27</u> W | <u>A-05</u> |
|                                    | T ___ R ___               | _____       |
|                                    | T ___ R ___               | _____       |
|                                    | T ___ R ___               | _____       |
| 2. Property Controlling in Section | S ___ T ___ R ___         | _____       |
|                                    | S ___ T ___ R ___         | _____       |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___         | _____       |
|                                    | S ___ T ___ R ___         | _____       |

RECEIVED FOR RECORD  
98 DEC -4 PM 3:48  
PAGE # 649 BK 5  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

(SAME AS CORNER M-05 T36N - R28W)

I, William Lenca, in a field survey on June 03, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey - Township Boundary - by H. Brevoort, Jr. - B.T.'s - Birch, 6" - N75°W - 18 lks.; Hemlock, 16" - S51°W - 40 lks. All original evidence for this corner has been destroyed by county road improvements.  
1852: Sectional Subdivision by Francis Coleman - B.T.'s - Cedar, 20" - N15°E - 08 lks.; Cedar, 18" - S50°E - 45 lks. All original evidence for this corner has been destroyed by county road improvements.  
1991: Land Corner Recordation Certificate Number 901 by William Lenca states, "Found 3/4" dia. Iron Pipe in center of C.R. N-S and in line with occupation East." TIES: 8" Tamarack Scr. NBT, N46°E, 60.00 feet; Nail in Power Pole, S79°E, 33.08'; Nail in 8" Elm, S88°W, 73.18'; Nail in 6" Spruce, N17°W, 130.40'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1/2" square Iron Bar inside of a 3/4" x 18" Iron Pipe and 4 witnesses as described in Land Corner Recordation Certificate Number 901 by William Lenca, RLS 26461. This position has been used for many years, fits existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum. cap stamped for corner location:

12" dia. Tamarack	N47°E	60.00 feet	Scr. NBT
6" dia. Cedar	S53°E	54.57 feet	Scr. NBT
8" dia. Cedar	S67°W	79.45 feet	Scr. NBT
6" dia. White Pine	N55°W	113.57 feet	Scr. NBT
Metal Survey Sign Post	S76°E	32.79 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date June 22, 1998