

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remuneration  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 10/1 1999  
Mr. Davis PLS  
Chairman

BK. 6 Pg. 101

RECEIVED FOR RECORD  
28 DEC 1999 3:56:09 PM  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
MENOMINEE (County)		
1. Public Land Survey	T 35N R 27W	F-01
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
(SAME AS CORNER F-13 T36N - R27W)

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5			4		3		2			1
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, William Lenca, in a field survey on Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1847: Original Survey by H. Floyd - B.T.'s - Sugar, 20" - N36°E - 31 lks.; Hemlock, 12" - N62°W - 23 lks. All original evidence for this corner has been destroyed by County Road improvements.  
1895: Plat of Survey by Justus Little recorded in Record of Surveys book in Register of Deeds Office shows this corner as it relates to other corners in Section 4, T35N-R27W. One tie is shown - "Pine Stump, 17, N62°E - 112.5 lks."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Due to county road improvements over the years, we were unable to recover evidence of the corner placed by Justus Little in 1895. We accepted the centerline of a 3 way county road intersection (roads run East - West - South) for this corner position. Measurements from this location to corners 1/2 mile West (2685.42 feet) and 1/2 mile East (2659.66 feet) fit reasonably well with those shown by Justus Little. This position also fits well with existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" N 45° E 39.58 feet @ sign post
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" S 38° E 48.83 feet 1 ft. E of power pole
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" S 10° W 85.12 feet 0.5 ft. N of cem. fnc. cor
- 7" dia. White Pine N 52° W 71.68 feet Scr. NBT
- Metal Survey Sign Post N 45° E 40.20 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 2, 1999

