

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Four Group Under Act 245 Of
P.A. Of 1970 on Dec 16, 1994
Mc Davis RLS

For corners in
MENOMINEE
(County)

Located In: _____ Corner Code ≠#

1. Public Land Survey	T	<u>36</u> N	<u>27</u> W	<u>J-09</u>
	T	R	R	_____
	T	R	R	_____
	T	R	R	_____
2. Property Controlling in Section	S	T	R	_____
	S	T	R	_____
3. Miscellaneous Property in Sec.	S	T	R	_____
	S	T	R	_____

RECEIVED FOR RECORD
04 DEC 27 AM 10:47
PAGE #174
BR. Y
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49859

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Lenca Mar. 31 19 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Cedar, 10" - N84°W - 89 lks; W. Pine, 12" - S23°W - 82 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1963: L.C.R.C. No. 798 (Vol. 3) by C.C. Lindgren, MSHD Survey Chief, states that a 1/2" dia. Iron Pin from Original Notes and existing data in approx. centerline of county road, 25' West from West end of bridge. TIES: SE End Wing wall - S45°E - 24.23'; NW End Wing wall - N15°E - 22.02'; 8" dia. Ash - N30°W - 76.11'. Ties are also shown to other Section Corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1/2 inch diameter iron rod 8 inches below the road surface in a location which matches the ties to the wing wall of the bridge as described in L.C.R.C. No. 798. Our measured distance to the Section Corner 1/2 mile East of 2696.27 feet matches well with Lindgren's recorded distance of 2696.6 feet. This corner position has been used by local surveyors for more than 30 years and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Aluminum cap stamped for corner location:

1/2" x 8" Iron in drill hole in NW Wing wall of bridge	N40°E	23.28 feet	
9" dia. Willow	S26°E	25.66 feet	Scr. NBT
7" dia. White Ash	S24°W	38.91 feet	Scr. NBT
6" dia. White Ash	N36°W	40.66 feet	Scr. NBT

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 14, 1994
Surveyor's Michigan License No. 26461