

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. of 1990 On 10/26, 19995
Mc Annis RLS
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE (County) Located In: Corner Code: ##

1. Public Land Survey	T	35N	R	27W	L-1
	T		R		
	T	36	R	27	L-13
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

RECEIVED FOR RECORD
 95 NOV - 8 AM 11: 32
 PAGE 9 242 BK 4
 BARBARA MONROE
 REGISTER OF DEEDS
 MENOMINEE COUNTY
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

(T36N-R27W - L-13)

I, William Lenca, in a field survey on Aug. 31, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd (Township Exterior) - B.T.'s - Hemlock, 8" - N36°E - 23 lks; Hemlock, 8" - N33°W - 15 lks. All original evidence has been destroyed by County Road improvements.
- 1985: L.C.R.C. No. 712 recorded by William Lenca, RLS No. 26461, states that a 1/2" dia. Iron Pin was set in the centerline of an East - West County Road and in line with ancient fences running North and South. TIES: 5" Ccd. - S04°W - 37.18'; 8" W. Birch - N50°W - 68.40'; 8" Ccd. - N36°E - 52.50'.
- 1989: Certified Survey No. 657 recorded by William Lenca, RLS No. 26461, shows Corner L-1 as it relates to Corner K-1 (NW Cor. Sec. 1, 35/27)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In an August, 1995 survey of Section 1, T35N-R27W, we found a 1/2 inch diameter Iron Pin in the centerline of County Road No. 358 (East - West), in line with ancient fences running North and South from this location, and in a location that matches with the record measurements in Certified Survey No. 657. We also found the 3 Bearing Trees recorded in L.C.R.C. No. 712, as described in part "A". This position has been used consistently for several years by local surveyors, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Sct 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

8" dia. Cedar	N61°E	73.24 feet	Scr. NBT
5" dia. Cedar	S37°E	51.11 feet	Scr. NBT
16" dia. Cedar	S53°W	74.53 feet	Scr. NBT
5" dia. Cedar	N38°W	58.64 feet	Scr. NBT
Metal Survey Sign Post	S04°E	31.8 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. All distances to trees are to nail in side of tree

Signed by William Lenca Date Sept. 06, 1995
 Surveyor's Michigan License No. 26461

242