

Approved by Menominee County  
 Local Survey Reestablishment  
 Four Corners Under Act 345 of  
 P.A. of 1995 On 12/26 1995  
McC Davis RLS

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE  
 (County)

Located In:

Corner Code ==

|                                    |   |           |     |           |
|------------------------------------|---|-----------|-----|-----------|
|                                    |   | 36N       | 26W | A-5       |
| 1. Public Land Survey              | T | _____     | R   | _____     |
|                                    | T | _____     | R   | _____     |
|                                    | T | <u>36</u> | R   | <u>27</u> |
|                                    | T | _____     | R   | _____     |
| 2. Property Controlling in Section | S | _____     | T   | _____     |
|                                    | S | _____     | T   | _____     |
| 3. Miscellaneous Property in Sec.  | S | _____     | T   | _____     |
|                                    | S | _____     | T   | _____     |

RECEIVED FOR RECORD  
 95 NOV -8 AM 11:32  
 PAGE # 247 BK 4  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 HENRIEVILLE, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

*Same as 1848-5-36N, R27W*

I, William Lenca, in a field survey on Mar 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett (Twp Linc) - B.T.'s - Tam, 6" - N38°W - 19 lks; Cedar, 12" - S38°W - 26 lks. All evidence for these B.T.'s was recently destroyed by construction of a gravel road.
- 1852: Original Survey (Section Subd.) by Francis Coleman -B.T.'s - Cedar, 10" - N50°E - 13 lks; Cedar, 12" - S36°E - 25 lks. Found remains of Cedar B.T. S36°E, 25 links. The other B.T. was recently destroyed by construction of a gravel road.
- 1984: L.C.R.C. No. 606 recorded by George B. Wilson, RLS No. 1760, states that a HDR Alum. Mon. was set from 4 original B.T.'s as described above. New Tics - Deep 1 magnets 1 foot North and 1 foot East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a survey of Section 7 in March of 1995 we found a 3/4" x 5' long aluminum rod/3-1/4" dia. aluminum cap as established in L.C.R.C. No. 606. The corner falls in the SE corner of a gravel lane running South and East from this location. In the construction of the gravel road, all evidence of the original B.T.'s except one (S36°E, 25 links) was destroyed. We accepted the above described monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Existing G. Wilson 3/4"x 60" Aluminum Pipe w/3 1/4" Alum. Cap Found 0.5' Below Surface of Gravel Drive:

|               |       |            |          |
|---------------|-------|------------|----------|
| 6" dia. Cedar | N52°E | 38.55 feet | Scr. NBT |
| 8" dia. Cedar | S45°E | 35.17 feet | Scr. NBT |
| 8" dia. Cedar | N65°W | 37.96 feet | Scr. NBT |
| 9" dia. Cedar | N08°W | 34.82 feet | Scr. NBT |



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date May 24, 1995  
 Surveyor's Michigan License No. 26461

247