

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1998 On 12/22 1999  
Met David RLS  
Chairman

Bk 6 Pg. 32

RECEIVED FOR RECORD  
28 DEC 1999 3:56:09 PM  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

For corners in	Located In:	Corner Code #
MENOMINEE (County)		
1. Public Land Survey	T 36NR 26W	A-7
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
SAME AS CORNER M-7, T36N-R27W

I, William Lenca, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s: Hemlock, 12" - S76°W - 38 lks; Birch, 15" - N66°W - 45 lks. All original evidence for this corner has been destroyed by farming activities.
- 1852: Original Survey (Sec. Subd.) by Francis Coleman - B.T.'s - Hemlock, 14" - N23°E - 22 lks; Hemlock, 16" - S56°E - 64 lks. All original evidence for this corner has been destroyed by farming activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner position falls on the southeast side of a farm field with ancient fences running East and West, and an ancient stone and wire fence running South. Due to clearing and farming activities, we were unable to find any evidence of the original post or bearing trees. Measurements from the fence intersection to other corners and occupations lines in the area fit well. We therefore accepted the location of the fence intersection as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

7" dia. Cherry	N62°E	55.87 feet	Scr. NBT
18" dia. Norway Pine	S20°W	16.80 feet	Scr. NBT
9" dia. Norway Pine	S72°W	49.91 feet	Scr. NBT
Twin 9" Cherry	N30°W	10.95 feet	Scr. NBT
Metal Survey Sign Post	South	1.0 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Sep. 1, 1999