

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>3</u> T. <u>36</u> N. S., R. <u>28</u> E. W.		<u>H-3, I-2, I-3</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**MENOMINEE  
CO.**

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were in a field survey on June 3 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

<u>H-3</u> South 1/4 corner Wood Post W. Pine 18 - S38°W - 50 L Fir. 6 - S36°E - 60	<u>I-2</u> East 1/4 corner Wood Post Beech 6 - N35°W - 40 L W. Pine 24 - S47°E - 31	<u>I-3</u> S.E. Section corner Wood Post Cedar 8 - N30°W - 8 links Cedar 11 - S52°E - 25 links Original evidence was reported, by local residents, to have been destroyed by construction of the county road.
--	--	---

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

H-3 Set on line between the S.E. and S.W. corners of Sec. 3 and in line with an old fence south. This also falls in the centerline of an E-W Co. Road and fits other occupation lines well.

I-2 Set from 28" W.P. Stp. S47°E-31 lks. For O.B.T. - Stp. is too rotted to show any marks but the stub of W.P. sight tree very plainly marked, falls on line about 7 chs. south another W.P. Stp. is in the proper position for a 16" W.P. line tree as recorded in the G.L.O. notes. Swamp call. both north and south fit very well

I-3 Set at G.L.O. record distance south of the stp. of a tam. line tree (recorded as tam. 10" dia. at 67.20 from the north) and in line with this stp. and the east 1/4 corner of Sec. 3 (The tam. stp. is now about 13 inches and shows the lower hack mark on both north & south sides in the over-

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner growth where the tree healed over.**

<u>H-3</u> 1" pipe 1/2" aluminum cap 7" R. maple N30°W 88.3' 8" R. maple N13°E 115.3'	<u>I-2</u> 1" pipe 1/2" aluminum cap Sq. cedar post 4" oak S65°W - 2.6' 8" stem of tw. oak N40°E - 16.4' 6" h. maple N42°W - 20.15'	<u>I-3</u> 1" pipe 1/2" aluminum cap 9" cedar S3°E - 50.8' 20" W. pine - N58°E - 67.0' 10" W. pine - N35°W - 31.0'
---	---	---

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_