

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>1</u> T. <u>36</u> N. S., R. <u>28</u> E. W.		<u>M-1, M-2</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MENOMINEE CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 12 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<p>M-1 N.E. Section Corner Wood Post Sugar 14 - N46°W - 36 } Lynn 14 - S51°W - 47 } not found</p>	<p>M-2 East 1/4 corner Wood post Fir 6 - S21°W - 17 Hem. 14 - N14 1/2°W - 36</p>
---	--

M-1 B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Set at record distance north from the stump of a white pine line tree noted as W. pine 40 inches in diam. at 69.65 on the east line of Sec. 1 - T36N-R28W and in line between said L.T. STP. and an 18" ± W.P. stub with a very definite blase and 2" or more of over growth believed to have been marked as a sight tree on the original gov't. survey. This stub is 482 ft. north of the twp. cor. The position of this corner as set fits record calls to hill, swamp edges, and streams as recorded in G.L.O. notes.

M-2 Set in centerline of E-W road and in line with old fence south. This position fits other occupation lines in the area well. No other evidence found

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>M-1 1" pipe, 4" aluminum cap 11" oak - N52°W - 7.8' 11" oak - S24°E - 16.6' 5" w. ash - N20°E - 19.0'</p>	<p>M-2 1" pipe, 4" aluminum cap 6" basswood - N35°W - 31.65' 8" oak - S70°W - 61.0' Face of 18" white oak - S09°E - 37.0' (Not marked)</p>
--	--

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____