

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>1</u> T. <u>36</u> N. S., R. <u>28</u> E. W.		K-2, L-1, L-2
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**MENOMINEE CO.**

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 19, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

### A. Description of original monument and accessories and/or subsequent restoration:

K-2	L-1	L-2
West $\frac{1}{4}$ corner	North $\frac{1}{4}$ corner	Center of Section
Wood post	Wood post	Not previously marked
Cedar 14 - N41°E - 10 L	Lynn 14 - N22°E - .32	
Cedar 14 - S87°W - 54 L	Sugar 14 - N42°W - .26	

### B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-2	L-1	L-2
Found point of old stake and axel shaft in willow swamp.	Set M:P.O.L. between the N.E. and N.W. section corners.	Set at intersection of N-S and E-W $\frac{1}{4}$ lines

### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2	L-1	L-2
1" pipe, 4" aluminum cap	1" pipe, 4" aluminum cap	1" pipe, 4" aluminum cap
8" poplar - N3°W - 107.5'	4" H. Maple - S46°W - 24.2'	Not marked
Remains of	7" poplar - N2°E - 12.9'	6" W. Birch-N63°E - 66.6'
16" cedar stp. - N34°E - 5.3'	18" oak - N57°W - 80.5'	Not marked
	Remains of	5" apple-N35°E - 72.2'
	42" W.P. Stp. - S67°E - 37.7'	Lower base only
		W. Birch-S60°W - 36.0'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_

DATE