

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY 3 T. 36 N. S., R. 28 E. W. G-2
2. PROPERTY CONTROLLING IN SECTION 3 T. 36 N. S., R. 28 E. W. 3. 8
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S., R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

MENOMINEE CO.
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 3 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
G-2 3/4 corner between 4/3 3 - N 1/16 between 4/3 8 - W 1/16 of Section 3
Wood post Not previously marked Not previously marked
B. Oak 10 - N50°W - 27
W. Birch 5 - S36°E - 21

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
G-2 Set on line between the N.W. & S.W. section corners of Sec. 3. - distance proportioned to G.L.O. record - an old W.P. stub, down but plainly blased on both sides, falls on line south of this corner.

3 - Set on line between the N.W. Sec. corner & the West 1/4 corner of Sec. 3 - distance proportioned to G.L.O. record.

8 - Set M.P.O.L. between the center post and the west 1/4 corner of section 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-2 1" pipe, 1/2" aluminum cap 3 - 1" pipe, 1/2" aluminum cap 8 - 1" pipe, 1/2" aluminum c:
4" R. maple N72°E - 12.5' 9" R. maple N10°E - 8.4' 10" R. maple N43°E - 25.6'
5" R. maple S11°E - 42.1' 3" hornbeam S44°W - 3.5' 10" W. Birch S2°W - 45.5'
9" R. maple S22°W - 15.2' 4" W. birch S48°E - 11.7'

SIGNED BY DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY DATE