

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|--------------|--------------------|
| 1. PUBLIC LAND SURVEY <u>3</u> T. <u>36</u> N. S., R. <u>28</u> E. W. | | <u>H-2</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>3</u> T. <u>36</u> N. S., R. <u>28</u> E. W. | | <u>7, 9</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

MENOMINEE CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 3 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|---|---|--|
| <u>H-2</u> C $\frac{1}{4}$ corner Section 3 Not previously marked. | <u>7</u> - N 1/16 between Sec. 3/2 Not previously marked | <u>9</u> - E 1/16 of Section 3 Not previously marked. |
|---|---|--|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-2 Set at the intersection of the N-S and E-W $\frac{1}{4}$ lines

7 - Set on line between the $\frac{1}{4}$ corner south and the section corner north. Distance prop. to G.L.O. record.

9 - Set M.P.O.L. between the center post and the E. $\frac{1}{4}$ corner of Section 3

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|--|---|---|
| <u>H-2</u> 1" pipe, 4" aluminum cap 8" cedar - N40°E - 14.4' 8" cedar - S14°W - 9.7' | <u>7</u> - 1" pipe, 4" aluminum cap 4" B. Spruce - S37°E - 15.9' 6' cedar - S50°W - 27.9' | <u>9</u> - 1" pipe, 4" aluminum ca 10" fir - N35°E - 50.8' 4" aspen - S26°E - 29.8' 3" W. spruce - S78°W - 28. |
|--|---|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____