

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 36-37 NR. 28 W.

Menominee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3, 4, 33 and 34.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 26" W. Pine stp. N 67 W 43 Links, marked S 33 NBT.

5" Aspen S 62 E 29 Links, marked S 3 NBT.

5" Aspen N 10 E 39 Links, marked S 34 NBT.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two W. Pine B.T.'s bearing N 57 E, 16 Links. Found notch and remains of overgrowth on stump. Stump in poor condition. Also bearing N 22 W, 31 Links, stump badly burned and in poor condition. Found W. Pine stump bottom S 45 E, 02 links.

Position checks well with section corner 1 mile west and 1/4 corner 1 1/2 mile east.

Corner found by Forestry Division Survey Crew.

Corner was placed and witnessed on 27 June 1958 with C. Linnert, District Forester, and Karl Baumann, Peshtigo, Wisconsin.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler

REGISTERED LAND SURVEYOR

DATE

4-29-59