

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R. 28W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner common to sections 23-24-25-26

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 7-5-61 with C. Limpert, D.F.

WITNESSES TO CORNER..... 8" W. Birch (S 25 NBT) S15°E 11½ links



5" Soft Maple (S24 NBT) N10°E 39 links

5" Hard Maple (S23 NBT) N60°W 60½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one W. Pine B.T. bearing S 39°W 30 links. B.T. is a stump 3' high, bottom blaze and scribe marks in good condition.

Corner found by C. Limpert.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 13, 1962
REGISTERED LAND SURVEYOR

Billy D. Buckler