

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 & 37 N.R. 28 W


Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 2-3, T36N R28W, 34-35, T37N R28W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 7/9/64 with A. Klawiter and R. Hinds

WITNESSES TO CORNER..... 10" White Pine (S3, NBT), S 87° W, 34 lks.



14" White Pine (S3, NBT), S 04° W, 26 lks.

10" R. Oak (S35, NBT), N 53° E, 16 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established on line and single proportioned distance between Section Corner to West and 1/4 Corner to East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 12/9/1964
REGISTERED LAND SURVEYOR