

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Menominee COUNTY


T 36 N R 28 W

DESCRIPTION OF CORNER Section corner for Sections $\frac{9}{10}$
 $\frac{16}{15}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5/4/71 F. J. Bray

WITNESSES TO CORNER..... 5" R. Maple (S. 10) (NBT) N 08° E, 18.3'



6" R. Oak (S. 16) (NBT) S 01° E, 12.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between the section corners 1 mile to the north, south, east and west. No original evidence was found. Wood post near.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 6-22-71
REGISTERED LAND SURVEYOR
Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68