

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Menominee COUNTY


T 36 N R 28W

DESCRIPTION OF CORNER Section corner for sections $\frac{22}{23}$
 $\frac{27}{26}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7-5-61 Billy D. Buckler

WITNESSES TO CORNER..... 8" Cedar (S27) (NBT) S 06 W, 19 $\frac{1}{2}$ links



7" Cedar (S26) (NBT) S 68 E, 16 $\frac{1}{2}$ links

10" W. Pine (S23) (NBT) N 01 E, 22 Links.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two down cedar stumps bearing N 58 E 42 links and S 65 W 45 links. Found old axe marks and overgrown blazes on cedar to SW.

Distance to swamp edges south, east and west and to good corners to south and east fit very well. This corner was set by Billy D. Buckler R.L.S.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

11-24-72