

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>1</u>	T. <u>36</u> N. <u>X</u> , R. <u>28</u> ^{XX} _{W.}	<u>K-1</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ S. _____ W. _____	_____
4. LOT NO. _____	RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____		_____

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 13, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

N.W. Sec. corner of Sec. 1 set in 1951 by Dean DeLamater

N.B.T.s	8" S. maple	S35W - 18 lks.
	6" S. maple	N38E - 30 lks.
	5" cedar	East - 22 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Re-witnessed Conservation Dept. monument as found. The two D. DeLamaters maple N.B.T.s had been cut but the stumps were in place showing rotted out bottom blazes. His cedar N.B.T. is still living but healed over. I re-marked it and scribed the new blazes. Found DeLamater's bearings to be considerably off. Remains of a large white pine stump with a slab showing the lower face and the bottom of the upper face is in place for the N.W. O.B.T. (white pine 24"-N78°W-16 lks.). Most of the scribing is burned and weathered away.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Michigan Department of Conservation monument

8" white pine	N88°W	122.0'
7" red maple	N42°W	19.3'

Re-marked Delamater N.B.T.

10" cedar	S81°E	14.2'
7" cedar	S40°E	11.0'

Remains of white pine stump of O.B.T. N74°W 10.7'

SIGNED BY

David B. Babbitt

DATE

19-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)