

SURVEY & REMONUMENTATION

APR 06 1999

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On 12/14 1998
Terence J. Wanie P.S.
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
 For corners in
MENOMINEE
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>36</u> N R <u>28</u> W	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
 99 DEC 14 PM 3:22
 PAGE# 675 BK5
 BARBARA HARRISON
 REGISTER OF DEEDS
 MENOMINEE MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on July 08, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - W. Pine, 16" - N48°E - 1.15 lks.; W. Pine, 22" - S29°W - 35 lks. All original evidence for this corner has been destroyed by logging activities.
- 1986: Plat of Survey by William Lenca shows this corner in relation to other corners in Section 32, T36N - R28W. The corner is shown as being on line and midway between Section Corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 3/4 inch diameter aluminum rod with a 3-1/4 inch diameter aluminum cap (HDR Monument) in a location fitting with a single proportional position. We accepted the existing corner monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



Accepted existing 3/4" Alum. Rod 5' long/3-1/4" dia. Alum. cap (HDR Monument) stamped for corner location:

4" dia. Oak	N12°E	20.07 feet	Scr. NBT
7" dia. Oak	S55°E	15.35 feet	Scr. NBT
14" dia. Oak	S21°W	22.45 feet	Scr. NBT
8" dia. Oak	N58°W	38.10 feet	Scr. NBT
Power Line	North	78.0 feet	
Carsonite Marker	South	1.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Oct. 13, 1998

675