

SURVEY & RECORDED

APR 06 1999

Approved by Menominee County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On 12/14, 1998  
Thomas S. Wanic P.S.  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

MENOMINEE  
(County)

Located In: Corner Code #

1. Public Land Survey	T 36N R 28W	F-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD  
50 DEC 14 PM 3:23  
PAGE # 692 BK 5  
SARAH A. ROBERTSON  
REGISTERED PROFESSIONAL  
MENOMINEE, WI 54956

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on July 08, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Aspen, 12" - N10°W - 59 lks.; W. Pine, 12" - S60°E - 78 lks. All original evidence for this corner has been destroyed by logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 3/4" x 36" Iron and rotted remains of a wood stake by doubling the distance and extending a line between the Northwest Corner and the West 1/16th Corner (Wisc - Mich. Power Company Monument) on the North line of Section 33, T36N - R28W. This location has been used by other surveyors, fits well with a G.L.O. swamp call 400' West, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 4' long Alum. Rod/3-1/4" dia. Alum. cap stamped for corner location in place of existing 3/4" x 36" Iron:

7" dia. Oak	N68°E	31.81 feet	Scr. NBT
10" dia. Oak	S43°E	31.36 feet	Scr. NBT
11" dia. Oak	S69°W	56.01 feet	Scr. NBT
12" dia. White Pine	N17°W	48.66 feet	Scr. NBT
Metal Survey Sign Post	North	1.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 16, 1998

