

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Recommendation
Peer Group Under Act 345 Of
P.A. Of 1989 On 12/14 1998
Thomas J. Wain PS
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36</u> N R <u>28</u> W	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
90 DEC 14 PM 3:23
PAGE # 691 B/L 5
BARBARA JOHNSON
REGISTER OF DEEDS
MENOMINEE MI 49850

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

(SAME AS CORNER F-01, T35N - R28W.)

I, William Lenca, in a field survey on July 08, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by H. Brevoort, Jr. - B.T.'s - Beech, 4" - N41°E - 06 lks.; Hemlock, 4" - N66°W - 17 lks. All original evidence for this corner has been destroyed by logging activities.
- 1959: L.C.R.C. No. 138 (Vol. 2) by Billy D. Buckler states, "This corner was re-established midway and on line between two Section corners. Corner lies 1.02 chains east of Power Line." Set 1" Pipe with 4" Brass Cap. TIES: W. Pine, 10" - N13°E - 93.5 lks.; Elm, 9" - S53°W - 165 lks.
- 1992: L.C.R.C. No. 736 (Bk 3) by Paul Bressette - SEE BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1" Pipe with a 4" Brass Cap and 2 B.T.'s in a location as indicated in Land Corner Recordation Certificate Number 138. We also recovered 4 B.T.'s as described in L.C.R.C. No. 736 (Book 3). The corner falls on the easterly edge of the clearing for an overhead transmission line. The corner was re-established by single proportion according to L.C.R.C. No. 138 (Vol. 2), and is therefore accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 1" Iron Pipe with 4" Brass Cap for corner location:

16" dia. W. Pine (Ex. B.T.)	N14°E	61.72 feet	Scr. NBT
9" dia. Maple (Ex. B.T.)	S78°E	38.79 feet	Scr. NBT
Ex. P.K./D.N.R. Tag in Power Pole	S02°E	114.99 feet	
6" dia. Maple	N24°W	31.54 feet	Scr. NBT
Metal Survey Sign Post	North	1.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 11, 1998

