

SURVEY & REMONUMENTATION

OCT 27 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Fee Group Under Act 345 Of
P.A. of 1980 On 10/11, 19999
McAnis RLS
Chairman

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

1. Public Land Survey

T 36N R 28W _____ G-12

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

RECEIVED FOR RECORD
99 OCT 15 PM 1:40
PAGE # 06 BK 6
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49859

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	
3													
4	7			8			9			10		11	
5													
6	10			17			16			15		14	
7													
8	19			20			21			22		23	
9													
10	30			29			28			27		26	
11													
12	31			32			33			34		35	
13													

I, William Lenca, in a field survey on Jun, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Beech, 12" - N76°E - 39 lks; Beech, 12" - S60°W - 59 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

After a careful search of the corner area, we found no evidence of the original corner accessories, or evidence of subsequent restoration. We therefore set the corner in the centerline of an East - West County Road and in line with an ancient fence line running North. This position lines up with the West Line of a cut-over area to the South, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

7" dia. Oak	N45°E	65.47 feet	Scr. NBT
20" dia. Norway Pine	S35°E	102.46 feet	Scr. NBT
8" dia. Maple	S39°W	69.95 feet	Scr. NBT
6" dia. Oak	N32°W	55.33 feet	Scr. NBT
Metal Survey Sign Post	South	41.6 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sep. 27, 1999