

SURVEY & REMONUMENTATION

OCT 27 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Manominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1980 On 10/11 1999
McDavid RLS
Chairman

For corners in **SECTION**

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36</u> N R <u>28</u> W	<u>H-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORDS
99 OCT 15 PM 1:40
PAGE # 07 236 6
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on June, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11								●					
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Y. Pine, 18" - S38°E - 45 lks; Beech, 10" - N64°W - 30 lks. No original evidence for this corner was recovered.
- 1995: L.C.R.C. No. 209, Book 4, by Paul Bressette, RLS No. 37270 - Set DNR Monument at intersection of ancient fences E-W-S. Fits dist. to Sec. Cor W. & stream call East. TIES: Cherry, 8" - N10°E - 14.8'; R. Maple, 9" - N33°E - 42.9'; R. Maple, 10" - N65°W - 21.2'; Oak, 16" - N41°W - 50.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a standard DNR Monument at an ancient fence corner with fences running East - West and South. We also found 4 B.T.'s in location as described in L.C.R.C. No. 209, Book 4 (see part "A"). This position fits well with long standing lines of occupation and with measurements to corners 1/2 mile East and 1/2 mile West, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Existing 1-1/2" dia. Iron Pipe/4" Alum. Cap stamped for corner location (Standard DNR Monument)

8" dia. Cherry	N10°E	15.13 feet	(14.8' R) Scr. NBT
10" dia. R. Maple	N33°E	43.35 feet	(42.9' R) Scr. NBT
12" dia. R. Maple	N65°W	21.46 feet	(21.2' R) Scr. NBT
16" dia. Oak	N41°W	51.45 feet	(50.9' R) Scr. NBT
Metal Survey Sign Post	S45°E	1.3 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sep. 15, 1999