

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>36</u> N R <u>28</u> W	<u>K06</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED FOR RECORD  
 96 OCT -7 PM 3:25  
 PAGE # 353 BK 4  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 REGISTERED OFFICE  
 1500 W. WASHINGTON ST.  
 LANSING, MI 48202  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on July 02, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14	●	13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by Francis Coleman - B.T.'s - Fir, 8" - N32°W - 49 lks; Cedar, 14" - S67°E - 21 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner was set in line with county road centerline running North and South, and in line with an ancient fence line running East. This position fits well with the North 1/16 line as occupied by the centerline of an East - West County Road, and is within 3 feet of splitting the mile measurement along the East Line of Section 14 - North 1/2 mile = 2627.11 feet; South 1/2 mile = 2630.11 feet. We accepted this location as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

16" dia. Oak	N85°E	90.73 feet	Scr. NBT
30" dia. Oak	S25°E	86.80 feet	Scr. NBT
7" dia. White Ash	S47°W	92.21 feet	Scr. NBT
8" dia. Cherry	N42°W	108.28 feet	Scr. NBT
Metal Survey Sign Post	East	28.3 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
 Surveyor's Michigan License No. 26461

Date July 06, 1996