

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Four Group Under Act 345 Of
P.A. of 1988 On 12/19 19994
Mel Davis RLS
ACTING Chairman

For corners in

MENOMINEE
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>36N</u> R <u>28W</u> | <u>K-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

94 DEC 12 AM 8:50
RECEIVED FOR RECORD
PAGE # 103 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Lenca, in a field survey on June 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - Beech, 8", N48°E, 26 lks & W. Pine, 14", S39°W, 30 lks - found White Pine B.T. with scribe marks still visible.
- 1962: L.C.R.C. No. 370 - Billy D. Buckler, DNR Surveyor, set a 1" dia. Iron Pipe/4" alum cap & B.T.'s - 8" W. Birch - S15°E, 11.5 lks; 5" Soft Maple - N10°E - 39 lks; 5" Hard Maple - N60°W - 60.5 lks. Corner was set from Original W. Pine B.T.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1" dia. Iron Pipe/4" dia. Alum. cap (Standard DNR Monument) and B.T.'s as described in part "A", in place. Also found the original W. Pine B.T. with scribe marks still visible. We accepted this corner as a careful and faithful perpetuation of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" dia. Iron Pipe/4" dia. Alum. cap stamped for corner location (Standard DNR Monument):

12" dia. Maple	N14°E	25.80 feet	Scr. NBT
9" dia. Maple	S81°E	17.49 feet	Scr. NBT
12" dia. White Birch	S05°E	8.03 feet	Scr. NBT
7" dia. Maple	N56°W	40.05 feet	Scr. NBT
Survey Sign Post	S72°W	2.3 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Sep. 14, 1994

Surveyor's Michigan License No. 26461