

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1988 On 12/9 199 94  
Mr. Davis RLS

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

- |                                    |                           |                         |
|------------------------------------|---------------------------|-------------------------|
| 1. Public Land Survey              | T <u>36N</u> R <u>28W</u> | _____ <u>K-10</u> _____ |
|                                    | T _____ R _____           | _____                   |
|                                    | T _____ R _____           | _____                   |
|                                    | T _____ R _____           | _____                   |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____                   |
|                                    | S _____ T _____ R _____   | _____                   |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____                   |
|                                    | S _____ T _____ R _____   | _____                   |

RECEIVED FOR RECORD  
 94 DEC 12 AM 8:58  
 PAGE # 104 BK. 4  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE MI 49859

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Lenca

Jul 18

94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1852: Original Survey by Francis Coleman - B.T.'s - Lynn, 16", N07°W, 32 lks & Sugar, 08", S34°E, 39 lks - All original evidence for this corner has been destroyed by fire & logging activities.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

This corner was reset using single proportionate measurement between the Southwest Corner and the Northwest Corner of said Section 25. The 1/2 mile distances to the North and South of this location were measured at 2648.38 feet. This matches very closely to the GLO distance of 2649.24 feet. This corner location is accepted as a careful and faithful re-establishment of the position of the original corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 2-1/2" dia. Alum. Pipe 30" long/3-1/4" dia. Alum. cap stamped for corner location:

12" dia. Oak	N42°E	57.36 feet	Scr. NBT
12" dia. Oak	S50°E	12.21 feet	Scr. NBT
6" dia. Maple	S51°W	27.47 feet	Scr. NBT
10" dia. Oak	N55°W	25.88 feet	Scr. NBT
Carsonite Marker	S25°W	1.5 feet	

**NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.**

Signed by William Lenca

Date Sep. 14, 1994

Surveyor's Michigan License No. 26461