

OCT 27 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/11 1999
Mr. Davis RLS
Chairman

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36N</u> R <u>28W</u>	<u>K-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REGISTERED FOR RECORD
99 OCT 15 PM 1:41
PAGE # 15 BK 6
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SAME AS CORNER K-1, T35N-R28W

I, William Lenca, in a field survey on Apr., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by H. Brevoort - B.T.'s - Beech, 8" - N22°W - 10 lks; Maple, 6" - N46°E - 27 lks. - Not evident.
- 1852: Original Survey by Francis Coleman - B.T.'s - W. Pine, 14" - S15°E - 07 lks; W. Pine, 14" - S54°W - 37 lks. Remains of W. Pine stump - S15°E - 07 links (4.6') still visible.
- 1983: L.C.R.C. No. 583, Book 2, by David Babbitt, RLS No. 21558 - Set DNR Mon. from stump of SE OBT - axe hack marks on stump. (16" W.P. stump - S15°E - 4.6'). Falls in line with very old fence North. GLO Notes state "73.50 trail ENE" A trail falls in that exact position from this corner. TIES: 22" W. Pine - N22°W - 63.95'; 16" W. Pine - S62°E - 128.1'; 7" W. Pine - S71°W - 45.6'; 4" W. Pine - N15°E - 17.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1 inch diameter iron pipe with a 4 inch diameter Aluminum Cap stamped for corner location along with 4 B.T.'s in location as described in L.C.R.C. No. 583, book 2 (see part "A"). Since this corner was perpetuated from original evidence, we accepted the position of the existing monument as a careful and faithful perpetuation of the position of the original corner. NOTE: The centerline of the former Michigan/Wisconsin Railroad bed in 36 feet East of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Existing 1 dia. Iron Pipe/4" Aluminum Cap stamped for corner location.

7" dia. White Pine	N15°E	17.60 feet	Scr. NBT
8" dia. White Pine	S16°W	45.63 feet	Scr. NBT
9" dia. White Pine	S71°W	45.72 feet	(45.6' R) Scr. NBT
5" dia. White Pine	N43°W	28.76 feet	Scr. NBT
Metal Survey Sign Post	North	1.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Sep. 15, 1999
Surveyor's Michigan License No. 26461

