

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1980 On 12/19/94
Del Davis RLS
ACTING

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>36N</u> R <u>28W</u> | <u>M-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECEIVED FOR RECORD
94 DEC 12 AM 8:5
PAGE # 100 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 498558
Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on June 14, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by H. Brevoort - B.T.'s - W. Pine, 20", N32°W, 30 lks & Aspen, 14", S29°W, 50 lks. All original evidence for this corner has been destroyed by County Road improvements.
- 1979: L.C.R.C. No. 221 recorded by David Babbitt, RLS No. 21558, states that a 1" dia. Iron Pipe/4" aluminum cap was set on line between the W1/4 Cor. of Sec. 19 & the W1/4 Cor. of Sec. 30 & in the center of an E-W County Road. B.T.'s - 6" Twin Red Pine - N01°E - 54.5'; Power Pole - N70°E - 87.6'; 9" Cedar - S61°E - 139.3'; 4" W. Birch - S61°W - 52.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The Corner Monument described in LCRC No. 221 (mentioned in part "A") has been destroyed by county road improvements. A DNR Retracement Survey Map dated 1980 shows the relation of this corner position to the W1/4 Corner of Section 25 and the W1/4 Corner of Section 24 of T36N-R28W. We traversed between these corners and placed the corner position accordingly. We also found the B.T.'s mentioned in part "A" and found that they fit this position. We accepted this corner as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:

| | | | |
|----------------------------------|-------|-------------|----------|
| 5/8" x 24" Iron Rod/2" alum. cap | N75°E | 86.45 feet | |
| 10" dia. Cedar | S51°E | 139.42 feet | Scr. NBT |
| 6" dia. W. Birch | S67°W | 52.45 feet | Scr. NBT |
| 12" dia. Twin Red Pine | N05°E | 55.10 feet | Scr. NBT |
| Survey Sign Post | N03°E | 28.6 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Sep. 14, 1994
Surveyor's Michigan License No. 26461

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |



100