

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 37 N.R. 25


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{26}{25}$ $\frac{35}{36}$

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/15/67, Frank J. Bray

WITNESSES TO CORNER..... 8" Cedar (S26)(NBT) N 58° W, 47 Links



9" Cedar (S36)(NBT) S 64° E, 42 Links

10" Lening Cedar (NBT) S 26° W, 12 $\frac{1}{2}$ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from point of wood post which checks good with Spruce baldly rotted to SE and cedar which was chopped out to NW for original bearings and distances. Trees Blazed facing corner.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/27/67
REGISTERED LAND SURVEYOR