

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 25


Menominee COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections ²⁵/₃₆

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/15/67

WITNESSES TO CORNER..... 7" Hemlock (1/4S)(NBT) N 80° W, 35 Links



11" Hemlock (1/4S)(NBT) N 78° E, 44 1/2 Links

18" Hemlock (1/4S)(NBT) S 11° E, 62 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was - placed midway and on line between section corners to east and to west.
Blazed trees near, no original evidence.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/23/67
REGISTERED LAND SURVEYOR