

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 N.R. 25W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{11}{12}$ $\frac{14}{13}$

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/6/68, F. J. Bray

WITNESSES TO CORNER..... 11" W. Pine (S.11) (MBT) N 78° W, 35 links



8" Blazed Cedar N 67° E, 12 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and single proportioned distance between section corners one mile to north and to south. Three miles randoms were run N and S in original survey and corrected back. Old blazed cedar near and overgrowth on slab could be face of B.T.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/28/68
REGISTERED LAND SURVEYOR
Frank J. Bray