

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.'s 38 & 37 N.R. 25 W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections 35/36 T38N, R25W
2/1 T37N, R25W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/18/68, F. J. Bray

WITNESSES TO CORNER..... 4" B. Spruce (S.35) (NBT) N 52° W, 07½ links



10" Cedar (S.1) (NBT) S 75° E, 16 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from old wood post with points of older stakes found along side. Found overgrowth of notch of B.T. to SE. B.T. to NW chopped out. Rotted stump bottoms of B.T.'s to NE and SW. Squared aspen near.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/26/68
REGISTERED LAND SURVEYOR
Frank J. Bray