

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code $\neq$
1. Public Land Survey	T <u>37N</u> R <u>25W</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 12/22, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-7. North 1/4 corner of Section 22. Wood post. Bash 12 - N45E, 24 Lks.  
 Cedar 12 - S58W, 73 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7. Found 1 1/2" pipe driven in stream (stream appears to have moved easterly 6' to 8' from its position at the time of the original survey). A cedar stub, with both upper and lower faces and scribing plain on both is in place for the SW original bearing tree. Witnessed pipe as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7. 1 1/2" pipe - in stream. 11" y. birch S17E, 140.4'  
 11" maple S4W, 115.5'  
 4" cedar S57W, 53.3'  
 5" cedar S70W, 48.1'

Signed by David B. Babbitt Date 1-27-87  
 Surveyor's Michigan License No. RLS 21558