

RECEIVED FOR RECORD

1992 APR 28 AM 11: 10

PAGE # 934-Bk 3
HENRY GURUSH
REGISTER OF DEEDS
MENOMINEE, MI 49858

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>37N</u> R <u>25W</u>	<u>J-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>26</u> T <u>37N</u> R <u>25W</u>	<u>8,9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Paul R. Bressette, in a field survey on April 9, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J-10. Center Quarter corner of Section 26. Not set in original survey, no evidence of subsequent establishment.
- 8. West One-sixteenth corner of Section 26. Not set in original survey, no evidence of subsequent establishment.
- 9. East One-sixteenth corner of Section 26. Not set in original survey. Found a wood post 1' north and an iron t-bar westerly ±40' from monumented position

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-10. Corner established at the intersection of the North-South and East-West Quarter lines of Section 26.
- 8. Corner established mid-point and on-line between the West Quarter and Center Quarter corners of Section 26.
- 9. Corner established mid-point and on-line between the East Quarter and Center Quarter corners of Section 26.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-10. 1" pipe with 4" aluminum cap 12" W. Pine (1/4S, BT) N 45° E 26.3'; 5" R. Maple (1/4S, BT) S 18° E 6.75'; 7" R. Pine (1/4S, BT) S 46° W 30.25'; 6" W. Pine (1/4S, BT) N 30° W 20.15'.
- 8. 1" pipe with 4" aluminum cap 10" Hemlock (1/16S, BT) N 14° E 27.9'; 4" Hemlock (1/16S, BT) S 37° E 31.55'; 10" W. Pine (1/16S, BT) S 18° W 22.5'; 10" W. Pine (1/16S, BT) N 50° W 30.0'.
- 9. 1" pipe with 4" aluminum cap 9" Cedar (1/16S, BT) N 32° E 7.3'; 12" Cedar (1/16S, BT) S 28° E 16.5'; 8" Hemlock (1/16S, BT) S 62° W 3.4'; 7" Cedar (1/16S, BT) N 51° W 8.0'.

Signed by Paul R. Bressette Date 4-28-92
Surveyor's Michigan License No. 37270

939