

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>12</u> T <u>37N</u> R <u>25W</u>	<u>09</u>
	S <u>12</u> T <u>37N</u> R <u>25W</u>	<u>16</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Jeremy J. Pipp, in a field survey on 9/17/2013AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(09) Center-East One-Sixteenth corner of Section 12. Not set in original survey, no evidence of subsequent establishment.

(16) East One-Sixteenth corner common to Sections 12 and 13. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(09) Corner position established mid-point and on-line between the Center One-Quarter corner and the East One-Quarter corner of Section 12.

(16) Corner position established mid-point and on-line between the South One-Quarter corner and the Southeast corner of Section 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(09) DNR monument  
 5" Cedar N42E 10.40' (1/16S,BT)  
 6" Cedar S50E 26.42' (1/16S,BT)  
 11" Tamarack S52W 23.72' (1/16S,BT)  
 5" Cedar N60W 15.28' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

(16) DNR monument  
 6" Cedar N37E 20.81' (1/16S,BT)  
 6" Cedar S49E 10.58' (1/16S,BT)  
 5" Cedar S66W 10.81' (1/16S,BT)  
 5" Cedar N40W 17.43' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by Jeremy Pipp  
 Surveyor's Michigan License No. 50447



Date October 1, 2013

For the Michigan Department of Natural Resources, Forest Resources Division

20283

20284