

Approved by Menominee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 9/25 1996  
McLain RLS  
 Chairman

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T37N R 25W

A06

T R

T R

T R

T R

2. Property Controlling  
 In Section

S

T R

S

T R

3. Miscellaneous  
 Property in Sec.

S

T R

S

T R

RECEIVED FOR RECORDS  
 96 OCT -7 PM 3:26  
 PAGE # 363 BK 9  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SAME AS CORNER M-6 T37N-R26W .

I, William Lenca, in a field survey on May 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Ironwood, 4" - S47°W - 08 lks.; Sugar Maple, 10" - N59°W - 18 lks. No original evidence found - destroyed by fire and logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Finding no original evidence, or evidence of subsequent restoration, we re-established this corner by single proportionate method between the Northwest Corner (A05) and the Southwest Corner (A07) of Section 18, T37N-R25W. This location fits well with a GLO call to a swamp edge 2 chains south, and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

12" dia. Hemlock	S81°E	12.26 feet	Scr. NBT
7" dia. Balsam	S14°W	27.21 feet	Scr. NBT
8" dia. Hemlock	S83°W	21.79 feet	Scr. NBT
10" dia. White Ash	N02°W	39.39 feet	Scr. NBT
Metal Survey Sign Post	South	1.00 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
 Surveyor's Michigan License No. 26461

Date Sep. 24, 1996