

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1990 On 12/27 1996  
*Mr. David RLS*  
Chairman

For corners in

| <u>MENOMINEE</u><br>(County)       | Located In:       | Corner Code # |
|------------------------------------|-------------------|---------------|
| 1. Public Land Survey              | <u>T7N R 25W</u>  | <u>B07</u>    |
|                                    | T ___ R ___       | _____         |
|                                    | T ___ R ___       | _____         |
|                                    | T ___ R ___       | _____         |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____         |
|                                    | S ___ T ___ R ___ | _____         |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___ | _____         |
|                                    | S ___ T ___ R ___ | _____         |

RECEIVED FOR RECORD  
97 JAN 17 AM 8:45  
PAGE # 478, BK 5  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE MI 49888

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Dec. 16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  | ●  |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by George Adair - B.T.'s - Cedar, 14" - N70°E - 31 lks.; Cedar, 12" - S12°W - 18 lks. Found decayed stumps of both original B.T.'s in proper position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We computed the single proportional location for this corner, traversed in to it and searched the area. We found no evidence of the original B.T.'s or any old cedar stumps in this area. 89 feet North of this position is an ancient East - West fence line and 2 large Cedar stumps fitting the position of the original B.T.'s. The stumps are too decayed to determine markings, however the stumps are in proper position for the originals, cause the corner to fall on the ancient East - West fence line and within 2 feet of a proportional location for East - West position. We therefore accepted this location as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

|                                    |       |            |          |
|------------------------------------|-------|------------|----------|
| 6" dia. Yellow Birch               | N51°E | 17.90 feet | Scr. NBT |
| 7" dia. White Ash                  | S42°E | 34.05 feet | Scr. NBT |
| 6" dia. White Ash                  | S38°W | 20.53 feet | Scr. NBT |
| 9" dia. Triple Maples (South tree) | N15°W | 61.58 feet | Scr. NBT |
| Metal Survey Sign Post             | North | 1.1 feet   |          |



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Dec. 26, 1996