

P.A. Of 1990 On 12/21, 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mc Davis RL
Chairman

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey T37N R25W F01
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

RECEIVED
55 DEC 30 AM 9 08
BARBARA MOFFSON
REGISTERED PROFESSIONAL
SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
SAME AS CORNER F-13, T38N-R25W

I, William Lenca, in a field survey on Jun. 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1847: Original Survey by James H. Mullett - B.T.'s - Hemlock, 8" - N64°E - 18 lks.; Hemlock, 5" - N05°W - 22 lks. All original evidence for this corner has been destroyed by farming activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We computed the single proportional location for this corner, traversed in to it and searched the area. We found an ancient fence corner that fell midway between the Northeast Corner (G-1) and the Northwest Corner (E-1) of Section 4 and approximately 25 feet South of a straight line between these corners. We accepted the location of the ancient fence corner as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum. cap stamped for corner location:

6" dia. Ironwood	N04°W	26.80 feet	Scr. NBT
4" dia. Maple	S78°E	32.97 feet	Scr. NBT
8" dia. Maple	S04°W	27.78 feet	Scr. NBT
9" dia. Maple	S87°W	66.73 feet	Scr. NBT
Metal Survey Sign Post	N40°W	1.10 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by W. J. William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 26, 1996

450