

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T <u>37</u> N R <u>25</u> W | <u>G06</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

RECORDATION BOOK
PAGE # 441 BK. 5
56 DEC 30 AM 9:07
REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Jul. 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by George Adair - B.T.'s - Cedar, 12" - S22°E - 15 lks.; Cedar, 14" - N36°E - 10 lks. All original evidence for this corner has been destroyed by farming activities.
1985: L.C.R.C. No. 715 by George B. Wilson, RLS No. 17607, states: "Found evidence of both bearing trees - bearing and distance both check" - Set: HDR Bertsen Monument with Deep - 1 magnets 2' North & 2' East. Sketch on back shows this corner as it relates to other corners in Section 16, T37N-R25W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 3/4 inch diameter aluminum rod (5' long) with a 3-1/4 inch diameter aluminum cap (known as HDR Bertsen Monument) in position matching with distances shown on a sketch on the back side of L.C.R.C. No. 715. Stump remnants for both original B.T.'s are still visible, but too decayed to determine any blazes or markings. We accepted the existing monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted existing 3/4" dia. alum. rod/3-1/4" alum. cap stamped for corner location:

5" dia. Cedar	N40°E	19.10 feet	Scr. NBT
32" dia. Cedar	S86°E	34.57 feet	Scr. NBT
24" dia. Cedar	S11°W	23.74 feet	Scr. NBT
4" dia. Cedar	N35°W	6.37 feet	Scr. NBT
Metal Survey Sign Post	North	1.1 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 26, 1996