

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/21 1996
Mr. Davis Res
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>37</u> N R. <u>25</u> W	<u>101</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

95 DEC 30 11 30 AM '96
REGISTERED LAND SURVEYOR
434 BK 5

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SAME AS CORNER I-13, T38N-R25W

I, William Lenca, in a field survey on Jun 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Twp Bdy) by James H. Mullett -B.T.'s - Cedar, 10" - N48°E - 09 lks.; Cedar, 16" - N33°W - 21 lks. Original evidence destroyed by county road improvements.
- 1852: Original Survey (Sec Subd) by George Adair - B.T.'s - Hemlock, 10" - S31°W - 26 lks.; Hemlock, 24" - S31°E - 21 lks. Original evidence destroyed by county road improvements.
- 1981: Field Notes from Certified Survey No. 226 by William Lenca, RLS No. 26461, states a P.K. Nail was set in the intersection of County Roads - B.T.'s: Anchor Pole - N44°E - 59.34'; S. end culvert - S46°E - 37.35'; 6" Tamarack - S50°W - 82.93'; Power Pole - N37°W - 42.92'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a P.K. Nail in the intersection of County Roads running North - South and East - West. We also found a 6" Tamarack B.T. - S50°W - 82.93 feet and the stump of a Power Pole - N37°W - 42.92 feet. The position of the P.K. fits well with distances to other corners and occupation lines in the area, has been accepted and used for several years by local surveyors, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N44°E	58.23 feet	1.1' S. of Anch. to Tel. Box
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S64°E	74.82 feet	1.1' W. of Tel. Box
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N36°W	42.89 feet	1.1' S. of PP
8" dia. Tamarack (Existing B.T.)	S50°W	82.93 feet	Scr. NBT
Metal Survey Sign Post	N44°E	59.8 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 23, 1996

434