

P.A. Of 1996 On 12/27 1996  
Mc Davis RLS  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE  
(County)

Located In:

Corner Code #

- |                                    |                         |            |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey              | <u>T7N</u> <u>R 25W</u> | <u>I04</u> |
|                                    | T ___ R ___             | ___        |
|                                    | T ___ R ___             | ___        |
|                                    | T ___ R ___             | ___        |
| 2. Property Controlling in Section | S ___ T ___ R ___       | ___        |
|                                    | S ___ T ___ R ___       | ___        |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___       | ___        |
|                                    | S ___ T ___ R ___       | ___        |

REGISTERED LAND SURVEYOR  
WILLIAM LENCA  
No. 26461  
95 DEC 30 AM 9:06  
431 BK. 5  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

William Lenca

Nov. 06 96

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

1852: Original Survey by George Adair - B.T.'s - Hemlock, 10" - N26°E - 27 lks.; Hemlock, 10" - S44°W - 26 lks. Original corner evidence was destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a P.K. Nail set in the centerline of county roads North - South and West. Field notes in my office indicate that we found this P.K. nail in a 1988 survey and took the following ties to it: Power Pole - N47°W - 61.64 feet (Gone); NW Corner of bottom step of Church - N55°E - 68.32 feet (found); Power Pole - S05°E - 113.37 feet (found); 1/2" iron @ base of sign - S50°W - 53.30 feet (found). This corner has been accepted and used by local surveyors for several years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

|   |       |             |                      |
|---|-------|-------------|----------------------|
| NW Corner of Church Bldg                                      | N55°E | 82.89 feet  |                      |
| NW Corner of Residence foundation                             | S28°E | 142.19 feet |                      |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S45°W | 53.53 feet  | 0.5' NW of Rd Sign   |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N43°W | 45.37 feet  | 0.5' SE conc. marker |
| Metal Survey Sign Post  | N43°W | 46.8 feet   |                      |



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Dec. 26, 1996

431