

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located in: Corner Code #

1. Public Land Survey	<u>T37N</u> <u>R25W</u>	<u>I06</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

96 DEC 30 AM 9:06
PAGE # 429 BK 5
BARBARA J. JOHNSON
REGISTERED PROFESSIONAL
LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Sep. 17, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15	●	14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by George Adair - B.T.'s - Cedar, 30" - N34°W - 10 lks.; Hemlock, 20" - N33°E - 24 lks. Original corner evidence was destroyed by county road improvements.
- 1987: Certified Survey No. 533, recorded by William Lenca, RLS No. 26461, shows this corner as it relates to other corners in Section 15, T37N-R25W. The monument is not described and no B.T.'s are given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a Railroad Spike in the centerline of a North - South County Road set midway between the Northeast Corner (I-5) and the Southeast Corner (I-7) of Section 15, T37N-R25W. This matches the corner position as shown in Certified Survey No. 533. We accepted the location of the railroad spike as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N59°E	31.29 feet	0.5' NW of Tcd. Box
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S49°W	57.14 feet	1' E. of PP
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	West	23.86 feet	0.5' E. of Surv. Sign Po
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N23°W	62.06 feet	1' S. of Fcn. Post
Metal Survey Sign Post	West	24.4 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 26, 1996

