

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| <u>MENOMINEE</u> (County) | Located in: | Corner Code # |
|---------------------------------------|---------------------------|---|
| 1. Public Land Survey | T <u>37N</u> R <u>25W</u> | <u>105</u> J-05 |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |

REGISTERED FOR RECORD
 96 DEC 30 AM 9:06
 REC'D # 425 BK 5
 REGISTER OF DEEDS
 REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on May 02, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|---|----|---|---|----|---|---|----|---|---|----|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | | 4 | | | 3 | | | 2 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | | 9 | | | 10 | | | 11 |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | | | 17 | | | 16 | | | 15 | | | 14 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | | 21 | | | 22 | | | 23 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | | 28 | | | 27 | | | 26 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | | 33 | | | 34 | | | 35 |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by George Adair - B.T.'s - Hemlock, 10" - N52°W - 07 lks.; Cedar, 10" - S47°E - 19 lks. Original corner evidence was destroyed by county road improvements.
- 1988: L.C.R.C. No. 808, recorded by William Lenca, RLS No. 26461, states: "Found 3/4" dia. Iron Pipe lying 2' below gravel road surface. Reset corner in centerline of North - South county road and in line with fence West." Set 5/8" x 24" Iron Rod/Ident. cap: Nail in Power Pole - N40°E - 49.82'; 9" Cedar - S40°W - 42.73'; 8" Cedar - N34°W - 43.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8 inch x 24 inch iron rod with a plastic identification cap marked "MI 26461/WI 1569" in the centerline of a North - South County Road and in line with an ancient fence running West. We also found the 3 witnesses as described in L.C.R.C. No. 808 matched the position of the existing iron rod. This corner fits well with measurements to other corners in the area, has been accepted and used by local surveyors for several years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

| | | | |
|-------------------------------|-------|------------|----------|
| 8" dia. Balsam | N50°E | 43.44 feet | Scr. NBT |
| 12" dia. Cedar | S40°E | 70.85 feet | Scr. NBT |
| 9" dia. Cedar (Existing B.T.) | S40°W | 42.73 feet | Scr. NBT |
| 8" dia. Cedar (Existing B.T.) | N34°W | 43.20 feet | Scr. NBT |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 23, 1996
 Surveyor's Michigan License No. 26461



425