

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T7N R. 25W</u>	<u>K06</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

96 DEC 30 11 06  
 REGISTERED LAND SURVEYOR  
 PAGE # 423 BK 5  
 REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on May 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by George Adair - B.T.'s - Cedar, 10" - N23°E - 07 lks.; Tamarack, 12" - S06°W - 17 lks. No original evidence for this corner was recovered.
- 1968: L.C.R.C. No. 546 (Volume 3) recorded by Frank Bray, DNR Surveyor, states: "This corner was placed midway and on line between section corners to the north and south. Old wood post near and axe marks on stubs near but no original evidence found." Set 1" iron pipe with 4" alum. cap - B.T.'s: 8" Cedar - N83°E - 09 links; 5" Cedar - S65°W - 21 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1 inch diameter iron pipe with a 4 inch diameter aluminum cap stamped for corner location along with 2 B.T.'s as described in L.C.R.C. No. 546 (volume 3). This corner falls in a thick and wet cedar swamp with no occupational evidence. We accepted the existing monument as a careful and faithful reestablishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum. cap stamped for corner location:

9" dia. Cedar (Ex. B.T.)	N83°E	6.49 feet	Scr. NBT
9" dia. Cedar	S01°E	35.04 feet	Scr. NBT
9" dia. Cedar (Ex. B.T.)	S65°W	14.22 feet	Scr. NBT
8" dia Cedar	N10°E	13.73 feet	Scr. NBT
Metal Survey Sign Post	S30°W	0.9 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 26, 1996  
 Surveyor's Michigan License No. 26461

423