

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. of 1980 On DEC 16, 1994
McDermott BLS
ACTING Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------------------|
| 1. Public Land Survey | T <u>37N</u> R <u>25W</u> | _____ <u>M-1</u> _____ |
| | T _____ R _____ | _____ _____ |
| | T _____ R _____ | _____ _____ |
| | T _____ R _____ | _____ _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ _____ |
| | S _____ T _____ R _____ | _____ _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ _____ |
| | S _____ T _____ R _____ | _____ _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD
94 DEC 27 AM 10:46
PAGE # 168 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49853
Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on Oct 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Township Lines) by Henry Floyd - B.T.'s - Hemlock, 24" - N55°W, 06 lks; Beech, 08" - N72°E - 41 lks. All original evidence for this corner has been destroyed by logging activities.
- 1968: L.C.R.C. No. 689-Vol 3 by Frank J. Bray, DNR Surveyor, states that a 1" dia. Iron Pipe/4" dia. Alum. cap was replaced from a 3/4" dia. iron pipe with 2" ball on end. This pipe checks well with other corners in the area. No original evidence found. - New B.T.'s - 5" S. Maple - N31°W, 24 lks; 6" H. Maple - S61°E, 23.5 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1" dia. Iron Pipe/4" dia. Alum. cap set next to a 3/4" dia. iron pipe with 2" dia. ball on the end, and 2 Bearing Trees as described in part "A". Both DNR B.T.'s were found in good condition. We placed a nail in the sides of the existing B.T.'s and re-used them. Since the DNR distances were to the face of the trees, our distances are slightly longer. This corner position fits well with corners to the west and south of this location. We accepted the DNR Monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 1" dia. Iron Pipe/3-1/4" dia. Alum. cap stamped for corner location:

10" dia. Maple	N57°E	32.28 feet	Scr. NBT
9" dia. Maple - (Ex. B.T.)	S61°E	15.62 feet	Scr. NBT
8" dia. Maple	S41°W	48.26 feet	Scr. NBT
8" dia. Maple - (Ex. B.T.)	N31°W	15.98 feet	Scr. NBT
Survey Sign Post	N80°E	2.1 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 15, 1994
Surveyor's Michigan License No. 26461