

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 245 Of
P.A. of 1990 On DEC 16 1994
McL Davis RLS
ACTING Chairman

For corners in
MENOMINEE
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>37N</u> R <u>25W</u>	_____	_____ <u>M-2</u> _____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

RECEIVED FOR RECORD
94 DEC 27 AM 10:46
PAGE # 167 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 19853
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Lenca, in a field survey on Oct 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Township Lines) by Henry Floyd - B.T.'s - Cedar, 06" - N54°W, 13 lks; Spruce, 5" - S43°E - 16 lks. All original evidence for this corner has been destroyed by logging activities.
- 1968: L.C.R.C. No. 676-Vol 3 by Frank J. Bray, DNR Surveyor, states that a 1" dia. Iron Pipe/4" dia. Alum. cap was replaced from a scribed wood post set by M. McNabb in 1918 from original B.T. This B.T. has been chopped out and is down. Point of older wood post was found alongside scribed post. Blazed and squared trees near. - New B.T.'s - 6" Cedar - N37°E - 09.5 lks; 8" Cedar - S30°W, 07 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1" dia. Iron Pipe/4" dia. Alum. cap and 2 Bearing Trees as described in part "A". Both DNR B.T.'s were found in good condition. We placed a nail in the sides of the existing B.T.'s and re-used them. Since the DNR distances were to the face of the trees, our distances are slightly longer. Since Marcus McNabb set his post from an original B.T. and the DNR Monument was placed in the location of the McNabb Post, we accepted the DNR Monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 1" dia. Iron Pipe/3-1/4" dia. Alum. cap stamped for corner location:

9" dia. Cedar - (Ex. B.T.)	N45°E	6.63 feet	Scr. NBT
8" dia. Cedar	S41°E	22.20 feet	Scr. NBT
12" dia. Cedar - (Ex. B.T.)	S40°W	5.20 feet	Scr. NBT
12" dia. Spruce	N51°W	15.71 feet	Scr. NBT
Survey Sign Post	N90°E	1.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.



Signed by William Lenca Date Nov. 15, 1994

Surveyor's Michigan License No. 26461