

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37 NR. 27 W.

Menominee COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 20 and 29.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 7" Cedar S 21 W 73 Links, marked 1/4 S NBT.

7" Cedar S 30 E 70 Links, marked 1/4 S NBT.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Tamarack B.T. bearing S 59 W, 25 Links; stump badly splintered. Found overgrowth of face and notch. Also found Tamarack stump bottom bearing N 52 E, 9 Links.

Corner found by Forestry Division Survey Crew.

Corner lies 23 Links, north of Power Line and 60 links south of approximate center line of County Road.

Corner was placed and witnessed on 27 June 1958 with C. Limpert, District Forester.

SURVEYORS SEAL

SIGNED Billy D. Buckler
Billy D. Buckler DATE 4-28-59
REGISTERED LAND SURVEYOR